

Supplementary Specification Sheet

#1-3 Sludge Pump Building

Remove 3 tab 25 yr. composition shingle roofing – incl. felt
3 tab- 25 yr. composition shingle roofing – incl. felt
Ridge cap – composition shingles
Remove and replace drip edge

#1-4 Lab Building

Remove laminated – comp. shingle rfg. – w/ felt
Laminated – comp. shingle rfg. – w/ felt
Ridge cap – composition shingles
Remove and replace drip edge
Flashing – pipe jack
Flashing – pipe jack – split boot

#3-1 Water Plant Building

Remove and replace metal roofing – ribbed – 26 gauge – 1 1/8" to 1/2"
Remove additional charge for high roof (2 stories or greater)
Additional charge for high roof (2 stories or greater)
Ridge cap – metal roofing
Gable trim for metal roofing – 26 gauge
Sidewall flashing for metal roofing – 26 gauge
Remove and replace corrugated fiberglass roofing (greenhouse type)
Removal and replacement of skylights
Flashing – pipe jack – lead

Roof – 2 story (Water Plant)

Remove and replace standing seam metal roofing
Remove additional charge for high roof (2 stories or greater)
Additional charge for high roof (2 stories or greater)
Ridge cap – metal roofing
Gable trim for metal roofing – 26 gauge

Exterior- Water Plant

Remove and replace gutter/ downspout – box – galvanized – 7" 8"
Preplacement of guttering on older building
Remove and replace gutter/ downspout – box – aluminum – 7" 8"
Replacement of guttering on newer building

Miscellaneous

Dumpster load – approx. 20 yards, 4 tons of debris

#3-5 Storage Building

Remove and replace metal roofing – corrugates – 29 gauge – agricultural

Remove and replace corrugated fiberglass roofing (greenhouse type)

Removal and replacement of skylights

Ridge cap – 29 gauge

Miscellaneous

Dumpster load – approx.. 12 yards, 1-3 tons of debris

#6-1 Library Building

Remove and replace metal roofing – ribbed – 26 gauge – 1 1/8" to 1/2"

Ridge cap – metal roofing

Gable trim for metal roofing – 26 gauge

Neoprene pipe jack flashing for metal roof

Exterior- Library

Remove and replace gutter/ downspout – aluminum – 7" 8"

Remove and replace gutter/ downspout – box – aluminum – 6"

Replacement of 14 LF of downspout. No damage observed on box downspouts.

Miscellaneous

Dumpster load – approx.. 12 yards, 1-3 tons of debris

#7-1 City Hall Building

Remove and replace metal roofing – ribbed – 26 gauge – 1 1/8" to 1/2"

Ridge cap – metal roofing

Gable trim for metal roofing – 26 gauge

Neoprene pipe jack flashing for metal roofing

Remove and replace cap flashing – steel – large –

Exterior – City Hall

Remove and replace gutter/ downspout – box – aluminum – 6"

Removal and replacement of gutter along west elevation. No damage to downspouts

Remove and replace window screen, 1-9

Miscellaneous

Dumpster load – approx. 20 yards, 4 tons of debris

#7-2 Storage Building

Remove and replace metal roofing – ribbed – 19 gauge – up to 1”
Remove and replace eave trim for metal roofing – 29 gauge
Ridge cap – 29 gauge
Miscellaneous
Dumpster load – approx. 12 yards, 1/3 tons of debris

#9/1 Fire Station Building

Remove and replace metal roofing – ribbed – 26 gauge – 1 1/8” to 1/2”
Ridge cap – metal roofing
Gable trim for metal roofing – 26 gauge
Sidewall flashing for metal roofing – 26 gauge
Roof vent – turbine type 2.00 EA
Remove and replace furnace vent – rain cap and storm collar, 8”

Exterior- FD

Remove and replace gutter/ downspout – box – aluminum – 6”
Removal and replacement of gutter along west elevation. No damage to downspouts.

Miscellaneous

Dumpster load – approx. 20 yards, 4 tons of debris

#21-1 Concession Stand

Remove 3 tab – 25 yr. – composition shingle roofing – incl. felt
Repair sheathing – OSB – 1/2”* 1.00 LS
Repair of hole in sheathing on east slope
3 tab – 25 yr. – composition shingle roofing – incl. felt
Remove additional charge for steep roof – 10/12 – 12/12 slope
Additional charge for steep roof – 10/12 – 12/12 slope
Ridge cap – composition shingles
Remove and replace drip edge
Flashing – pipe jack – split boot

Exterior- Concession Stand

Comb and straighten a/c condenser fins – window unit*

#21-1 Restrooms

Remove 3 tab – 25 yr. – composition shingle roofing – incl. felt
3 tab – 25 yr. – composition shingle roofing – incl. felt
Ridge cap – composition shingles
Remove and replace drip edge
Flashing – pipe jack